

2020 Research Park Drive Suite 100 Davis CA 95618 530.756.5905 phone 530.756.5991 fax westyost.com

### TECHNICAL MEMORANDUM

DATE: February 14, 2024

Project No.: 1088-60-23-02

- TO: Chad Davisson, General Manager Graton Community Services District
- FROM: Anne Girtz, PE. RCE #91396
- REVIEWED BY: Ryen Tarbet
- SUBJECT:Graton Community Services DistrictSanitary Sewer System Condition Assessment Technical Memorandum Draft

#### INTRODUCTION

Graton Community Services District (District) is undertaking a project to assess the condition and plan for rehabilitation and repair of its sanitary sewer collection system.

This technical memorandum (TM) presents the methodology, results, and recommendations from the condition assessment that was performed on the District's sanitary sewer collection system, including gravity pipelines, manholes, and lift stations.

The following sections of this TM include:

- Background
- Existing System Description
- Condition Assessment Methodology, Results, and Repair & Rehabilitation Recommendations
  - Gravity Mains
  - Manholes
  - Lift Stations
- Next Steps

#### BACKGROUND

The District received a grant from the State Water Resources Control Board in March 2020 for planning, environmental, and design services for a project that would address deficiencies in the District sewer collection system (Agreement C-06-8335-110). The original scope of work included closed circuit television (CCTV) inspection of collection system infrastructure, a preliminary rehabilitation report, environmental documentation, CWSRF funding application support, and 50-percent design and bid documents to support rehabilitation and repair of the collection system.

The Water Board issued an Amendment to the agreement (Amendment No. 1) on June 9, 2023, which revised the scope and schedule of the project. Based on discussion with the District after issuance of

Amendment No. 1, the scope of work was modified to expand collection system inspection efforts to include cleaning and inspection of all 32,000 feet of sewer line, inspection of 132 manholes, and inspection of the two collection system lift stations. With this expansion of the condition assessment efforts, it is not expected to be possible to complete all the scope items (specifically, the intertie pipeline assessment or the evaluation of the treatment plant disinfection system) unless the budget for the project is increased. To make the most efficient use of the available funding, the District agreed to move forward with the collection system condition assessment efforts in parallel with continuing discussions with Water Board staff regarding options for further modifications to the agreement. This includes discussing whether the total budget for the agreement can be increased so that all the planning efforts necessary to support the District's long-term goals can be completed.

This TM presents a summary of the condition assessment that was performed on the District's sanitary sewer collection system assets, including gravity mains, manholes, and lift stations. This document will be used to understand the District's rehabilitation needs and define the recommendations for the Preliminary Design Report to be completed in a next phase of the project and used to support a construction grant application.

#### **EXISTING SYSTEM DESCRIPTION**

The District is located west of Santa Rosa, bounded by Sebastopol to the south, Occidental to the west, and Forestville to the north. The District provides sanitary sewer collection, treatment, and disposal to a population of approximately 1,600 (2018) over a service area of approximately 43.1 acres. The sanitary sewer facilities are owned by the District.

The existing sanitary sewer collection system is made up of approximately 7 miles of gravity pipeline, ranging from 6 to 12-inches in diameter. Two lift stations convey flow from parts of the collection system to the trunk on Ross Road, and then onto the District wastewater treatment facility, which is located at the north-westernmost part of the service area. The majority of the system (approximately 32,000 linear feet of gravity pipeline and the two lift stations) was constructed around 1976 and is now 48 years old. Development and system expansion after 1976 added approximately 5,000 linear feet of pipeline to the system. Most of the pipelines installed in 1976 are believed to be asbestos cement (AC) pipe; pipelines installed later are typically plastic (PVC, PE). Table 1 summarizes the gravity pipelines by diameter. The service area and collection system are presented in Figure 1.

Т	able 1. Sanitary Sewer Gr	avity Pipelines by Diamete	r
Pipe Diameter, inches	Length of Pipelines, ft	Length of Pipelines, miles	Percent of System
6	28,644	5.4	77%
8	3,444	0.7	9%
12	4,888	0.9	13%
Total	36,977	7.0	100%



Prepared by:





Graton Community Services District Sewer Rehab and Replacement Phase 1

Prepared for:





#### Wastewater Treatment Plant



Lift Station



Manhole

- Cleanout •
- Gravity Main (6-inch)
- Gravity Main (8-inch)
- Gravity Main (12-inch)
- --- Force main
- Service Area



**Existing Wastewater Collection System** 

### CONDITION ASSESSMENT METHODOLOGY AND RESULTS

This section presents the condition assessment methodology and results for gravity pipelines, manholes, and lift stations.

#### **Map Digitizing and System Verification**

Prior to any condition assessment, the existing mapping – consisting of PDF record drawings – was digitized into an ArcGIS online database and map. The database included spatial location of pipelines and manholes and associated asset attributes (e.g., size, material, installation date, etc.). A snip from the ArcGIS online map is presented in Figure 2. Once the map was prepared, field visits were performed to locate and GPS manholes, and to verify the connectivity of the system. The field collected GPS coordinates of manholes were used to update the ArcGIS online mapping. The field-verified ArcGIS online mapping became the basis for the pipeline and manhole inspections.




Figure 2. Graton CSD ArcGIS Online Map

#### **Gravity Pipelines**

Gravity pipelines were assessed using CCTV inspection. Inspections followed the National Association of Sewer System Companies (NASSCO) Pipeline Assessment Certification Program (PACP) assessment standards.

#### Inspection

CCTV inspections were performed by Miksis Services Inc. (MSI) in September and November 2023. All pipelines were hydro-jetted prior to inspection to remove debris. Table 2 presents a summary of the CCTV inspection status.

Table 2. Pipeline CC	TV Inspection	n Status		
Inspection Status	Count of Pipelines	Length of Pipelines, ft	Length of Pipelines, miles	Percent of System
Complete Inspection	114	27,968	5.3	76%
Partial Inspection - Complete for assessment purposes	17	4,626	0.9	12%
No Inspection Possible (No Access)	12	2,193	0.4	6%
No Inspection	16	2,190	0.4	6%
Total	159	36,977	7.0	100%

As presented in Table 2, full CCTV inspections were completed for 76 percent of the system; and partial inspections (adequate for condition assessment purposes) were completed for 12 percent of the system. The remaining 12 percent of the system was not inspected; this was due to access (not found or access was not possible) and schedule constraints. Results of the completed inspections will be extrapolated to uninspected parts of the system for purposes of rehabilitation and repair planning in this TM.

#### **Condition Assessment**

The CCTV inspections were used to assess the pipelines according to NASSCO's PACP standards. PACP classifies pipe defects as either structural or operation and maintenance (O&M) related. Structural defects provide an indication of the condition and structural degradation of the pipe, and include defects such as holes, cracks, breaks, and fractures. O&M defects provide an indication of the operational condition of the pipe and are related to maintenance issues such as deposits (grease, sediment), roots, or inflow and infiltration (I&I). All identified defects are assigned a corresponding defect grade based on their risk of further deterioration or failure (from least severe – Grade 1, to most severe – Grade 5). Defect Grade severity definitions for structural and O&M defects are presented in Table 3.

	Table 3. PACP Defect Grade Definitions <sup>1</sup>
Defect Grade	Severity Definition
Grade 5	Pipe segment has failed or will likely fail within the next five years - requires immediate attention. Pipe segment has more than thirty percent (by pipe area) of flow restricted.
Grade 4	Pipe segment has severe defects - risk of failure within the next five to ten years. Pipe segment has between twenty to thirty percent of flow restricted.
Grade 3	Pipe segment has moderate defects - deterioration may continue, at a ten to twenty-year timeframe. Pipe segment has between ten and twenty percent of flow restricted.
Grade 2	Pipe segment has minor defects - pipe unlikely to fail for at least 20 years. Pipe segment has less than ten percent of flow restricted.
Grade 1	Pipe segment has minor defects - failure unlikely in the foreseeable future.

<sup>&</sup>lt;sup>1</sup> Condition Assessment of Underground Pipes, U.S. EPA Water Infrastructure Outreach, 2015

#### Results

Table 4 and 5 present a summary of the pipeline condition assessment results by PACP structural or O&M defect Grade. 33 percent of assessed pipelines have no structural defects. The most prevalent structural defects are offset joints, broken pipe, and cracks. Photos showing some structural defects are below. Figure 3 presents the Structural condition of the pipelines, with each pipe symbolized by its maximum Structural defect Grade.

Table 4. Pipeline Condition Assessment Summary – Structural Defects			
Maximum Structural Defect Grade	Count of Pipelines	Length of Pipelines, feet	Percent by Length
Grade 5	12	3,219	9%
Grade 4	19	5,152	14%
Grade 3	38	10,165	27%
Grade 2	6	1,655	4%
Grade 1	1	303	1%
No Structural Defects	55	12,099	33%
Not Inspected	16	2,190	6%
No Inspection Possible (No Access)	12	2,193	6%
Total	159	36,977	100%



Offset Joint - Large (camera rotated 90° clockwise)



Offset Joint - Large



Photo 3. Hole/Broken with Voids Visible

68 percent of assessed pipelines have no O&M defects. The most prevalent O&M defects are deposits and roots. Details on pipeline defects are provided in Attachment A – Pipeline Database.

Table 5. Pij	peline Condition Asses	sment Summary – O&M D	efects
Maximum O&M Defect Grade	Count of Pipelines	Length of Pipelines, feet	Percent by Length
Grade 5	3	864	2%
Grade 4	7	1,816	5%
Grade 3	3	1,038	3%
Grade 2	9	2,392	6%
Grade 1	5	1,312	4%
No O&M Defects	104	25,172	68%
Not Inspected	16	2,190	6%
No Inspection Possible (No Access)	12	2,193	6%
Total	159	36,977	100%



Prepared by:





Graton Community Services District Sewer Rehab and Replacement Phase 1

Prepared for:

Wastewater Treatment Plant WWTP

- Lift Station LS
- Manhole 6
- Cleanout
- --- Force main

Maximum PACP Structural Defect Grade

- 5 2
  - 0 (No Defects)
  - Unknown



#### **Rehabilitation and Repair Recommendations**

Preliminary recommendations for rehabilitation and repair (R&R) were developed based on the pipeline condition assessment.

It is recommended that all PACP Grade 3 and higher defects are addressed with an R&R or maintenance action. These recommendations are consistent with industry best practices and the goals of the District to correct deficiencies in system. Table 6 describes each of the potential actions, and the criteria used to assign an action to each pipe.

	Table 6. R&R or Maintenance Actions		
Action	Description	Suitable Defects, Criteria	
R&R Action			
Cured-in-Place Pipe (CIPP)	CIPP lining is a technology that deploys an impermeable liner within the pipeline that is then expanded and cured to form to the pipe profile. The liner is chemically adhered to the pipe wall for a rigid, impervious liner installation, designed to perform as a complete structural pipe that does not rely on the host pipe for support. CIPP can be applied as an isolated repair, or a full pipeline repair.	<ul> <li>Suitable for non-protruding defects (cracks, holes)</li> <li>Not suitable for offset joints</li> <li>Isolated CIPP is suitable for defects &lt;10ft in length</li> </ul>	
Excavate and Repair (Full Replacement and Spot Repair)	Excavate and repair rehabilitation involves open-cut trench excavation to expose the pipeline and either repair an isolated segment (spot repair) of the pipeline or the entire pipeline (full replacement). This is the most invasive technology requiring larger construction areas, trench shoring, and dewatering. Pipe bursting could also be used for full pipeline replacements, as pipe material and site constraints allow.	<ul> <li>Suitable for protruding defects and structural sags</li> <li>Spot Repairs are suitable for defects covering &lt;50% of the pipe length; for defects that cover &gt;50% of pipe length, Full Replacement</li> </ul>	
Maintenance Action			
Heavy Cleaning	Cleaning efforts prior to CCTV included at a minimum two passes of hydrojetting. Heavy cleaning was performed in several locations to clear the pipe enough for inspection. Heavy cleaning is required for pipes that were not able to be completely cleared/cleaned during the inspections.	<ul> <li>Suitable for debris, deposits, grease, encrustation</li> </ul>	
Root Removal	Root removal by mechanical (root cutting) or chemical (root foaming) means. Pipes with severe root intrusion may CIPP lined after to root removal to prevent future root issues.	Suitable for roots	

Based on the criteria in Table 6, each pipe with a structural or O&M defect of Grade 3 or higher was assigned a recommended R&R or maintenance action. Engineering judgment was also used to review and recommend pipes for action; for example, a pipe with Grade 2 spalling throughout its entire length was recommended for CIPP rehabilitation. Recommended actions are summarized in Table 7. Pipeline R&R recommendations are presented in Figure 4.

Table 7. Pipeline R&R and Maintenance Recommendations			
R&R Recommendation	Count of Pipelines	Length of Pipelines, feet	Percent by Length
Replacement	16	4,579	12%
CIPP	12	2,891	8%
Spot Repair(s)	42	11,445	31%
Maintenance Only	6	1,513	4%
No R&R Required	55	12,166	33%
Unknown - Not Inspected	16	2,190	6%
Unknown - No Inspection Possible	12	2,193	6%
Total	159	36,977	100%

#### **Recommendations for Pipelines Not Inspected**

R&R recommendations were extrapolated to pipelines within the system that were not inspected (Unknown rows in Table 7) using ratios of R&R action of inspected pipelines to total inspected pipelines. R&R is expected on approximately 16 additional pipelines of the 28 pipelines that were not inspected; this includes 4 pipes to be replaced; 2 for CIPP, and 10 for spot repair). Table 8 presents the expected R&R recommendations for the entire District system. Consideration will be made during development of the detailed design documents to account for expected additional pipeline inspection, condition assessment, and R&R.

Table 8. Expected Pipelin	ne R&R Recommendat	ions (including pipelines i	not inspected)
R&R Recommendation	Count of Pipelines	Length of Pipelines, feet	Percent by Length
Replacement	20	4,887	13%
CIPP	14	3,280	9%
Spot Repair(s)	52	12,984	35%
No R&R Required	73	15,827	43%
Total	159	36,977	100%



Prepared by:





**Graton Community Services District** Sewer Rehab and Replacement Phase 1

Prepared for:

WWTP	Wastewater Treatment Plant
------	----------------------------

- Lift Station
- Manhole
- Cleanout
- --- Force main
  - ----- No R&R Required
- Maintenance Only
- Spot Repair
- CIPP
- Full Replacement
- Unknown Not Inspected
  - Unknown No Inspection Possible



Pipeline R&R Recommendations

#### Manholes

Manhole inspection was performed according to the NASSCO Manhole Assessment Certification Program (MACP) Level 1 assessment standards which consists of a general visual assessment from the exterior of the manhole frame. This includes observation notations, and photographs of the manhole barrel, cover, and interior.

#### Inspection

Manhole inspections were performed by West Yost and SKL Solutions (SKL) from August 29, 2023 to February 2, 2024. Table 9 presents a summary of the manhole inspection status.

Table 9. Man	hole Inspection Status	
Inspection Status	Count of Manholes	Percent of Total Manholes
Complete Inspection	96	83%
Not Inspected	2	2%
No Inspection Possible (Not Found or No Access)	17	15%
Total	115	100%

As presented in Table 9, manhole inspections were completed for 83 percent of all manholes. 17 percent of manholes were not inspected, mostly consisting of manholes that could not be found or accessed; two of these manholes were not able to be inspected due to schedule constraints. Results of the completed inspections will be extrapolated to uninspected manholes for purposes of rehabilitation and repair planning in this TM.

#### **Condition Assessment**

The MACP Level 1 inspection rates the condition of seven manhole component including cover, frame, chimney, cone, wall, bench, and channel. Ratings include: Sound (no defects, good condition); Broken (e.g. the manhole cover is broken and is in loose pieces, manhole ring is broken, or pieces of the manhole frame are missing); Defective (manhole component has visible structural or O&M Defects); or Corroded (manhole component shows signs of corrosion).

#### Results

Table 10 presents a summary of the manhole condition assessment results, with component conditions ordered from most to least severe. Details on manhole defects are provided in Attachment B – Manhole Database.

63 percent of manholes have no defects. The most prevalent defect observed in manholes was corroded frames and covers. Many manholes (46) were observed to have infiltration staining. Other issues observed in the field, and not recorded in the standardized inspection included: Many manhole covers are slurry sealed-over and are very difficult to open; many manholes have their pick-holes plugged (assumed intentionally for I&I prevention) and are very difficult to open.

Table 10. Manhole Condit	ion Assessment Summa	ıry
Component Condition and Quantity	Count of Manholes	Percent of Total Manholes
Broken or Cracked	0	0%
Defective or Corroded: Greater than 3 Components	6	5%
Defective or Corroded: 3 Components	2	2%
Defective or Corroded: 1 to 2 Components	17	15%
Sound (No Defects)	73	63%
No Assessment Possible (Not Found or No Access)	17	15%
Total	115	100%

#### **Rehabilitation and Repair Recommendations**

Based on the types and quantity of defects observed, it is recommended that manholes with greater than three defective components (including both Defective and Corroded in Table 10) are replaced. Manholes with three defective components are recommended to be rehabilitated. Manholes with less than three defective components could be rehabilitated, if the District chooses, but are generally in acceptable structural condition. Manholes with infiltration staining could also be considered for lining to reduce inflow and infiltration, based on priorities of the District.


Manhole rehabilitation can include manhole lining, grouting, reconstruction of channels, replacement of frame and cover, and other methods. The specific manhole rehabilitation method will be determined during the design phase based on detailed condition assessment information. Table 11 summarizes the manhole R&R recommendations. Manhole R&R recommendations are presented in Figure 5.

R&R Recommendation	Count of Manholes	Percent of Total Manholes
Replacement	6	5%
Rehabilitation (Method to be determined in detailed design)	2	2%
No R&R Required <sup>(a)</sup>	90	78%
Unknown (Not Found/Not Accessible)	17	15%
Total	115	100%

reduce I&I and extend the life of manhole assets.

#### **Recommendations for Manholes Not Inspected**

R&R recommendations were extrapolated to manholes within the system that were not inspected using ratios of R&R action of inspected manholes to total inspected manholes. Manhole replacement is expected on one additional manhole of the 17 manholes that were not inspected. Consideration will be made during development of the detailed design documents to account for expected additional manhole inspection, condition assessment, and R&R.



Prepared by:





**Graton Community Services District** Sewer Rehab and Replacement Phase 1

.

Prepared for:

#### Wastewater Treatment Plant

- Lift Station
- Gravity Main
- --- Force Main

### Manhole R&R Recommendations

- Replacement
- Rehabilitation (Method to be determined)
- No R&R Required
- Unknown (Not Found/Not Accessible)
- Cleanout



Manhole R&R Recommendations

### **Lift Stations**

The District owns and operates two lift stations. Lift Station 1 is a submersible pump station (two pumps) with a wet well and a single room electrical/generator building, located at 3400 Ross Road. Lift Station 1 collects wastewater from areas of town south of 3400 Ross Road and conveys flow via an 8-inch diameter, 1,700-ft long force main, discharging to a gravity sewer manhole on Ross Road just north of Falcon Lane. Lift Station 2 is a grinder submersible pump station (two pumps) in a wet well, located adjacent to 3820 Ross Road in a residential area. Lift Station 2 collects wastewater from the two adjacent residential lots and conveys flow via a 1.5-inch diameter, 130-ft long force main, discharging to a 6-inch gravity main which connects to the Ross Road sewer main. Both stations and force mains were originally constructed around 1976 and have had limited upgrades since.

Lift station condition assessments were conducted on August 21, 2023 by two West Yost engineers, escorted by John Gibson, the Chief Wastewater Treatment Plant Operator and Chad Davisson, District General Manager.

Condition assessment included visual inspection of major lift station assets such as pumps, wet well/drywell, inlet/outlet piping, and electrical/instrumentation. Operator feedback was collected to understand current operating and maintenance issues. Both a condition and performance score were assigned to assets on a scale of 1 to 5, with 5 indicating the worst condition or performance (see Table 12).

		Table 12. As	set Condition As	ssessment Rating	gs	
				Rating		
Rating	Description	1	2	3	4	5
Condition	Assesses the physical condition of the asset.	Excellent	Slight Visible Degradation	Visible Degradation	Integrity Moderately Compromised	Integrity Severely Compromised
Performance	Assesses the performance of the asset based on its intended function.	Functioning as intended	In service, but elevated O&M costs	In service, but function is moderately impaired	In Service, but Function is Highly Impaired	Not Functioning as Intended

#### **Results and Recommendations**

A summary of the condition assessment results and recommendations for lift stations are presented in Table 13 (Lift Station 1) and Table 14 (Lift Station 2). Photos of each station are included after each table. Priority replacements are indicated in the grey cells. Other recommendations would improve the operation, reliability, or access of the facilities but are second in priority.

			Table 13. Lift Station 1 – Condition Assessment Results and Recommendations	
Asset	Condition Rating	Performance Rating	Comments	
Pump 1	5	5	Out of service, sent in for repairs/quote. Pumps are likely not operating at design capacity or incoming flow is greater than pumps are designed for.	Replace. New pump capa add
Pump 2	3	3	Pumps are likely not operating at design capacity or incoming flow is greater than pumps are designed for.	
Pump Guide Rails	3	3	Pumps are mounted on a bracket adapter to work with the guide rails. Guide rails are not standard width. See Photo 1 below.	Replace guide rails with pur
Wet Well	1	1	Cleaned and vactored every year. Wet well is in good structural condition. See Photo 1 below.	
Wet Well Lid	3	1	Minor corrosion; 1 of 4 support brackets gone due to chains hanging on them; chains have since been moved. Hatch does not contain safety grate or spring assist mechanism for opening the hatch.	Replace or modify hatc
Discharge piping in wet well	4	3	Corrosion along entire section. See Photo 1 below.	
Water Service Well	3	1	Well on site, shared ownership with neighbor	
Valve Vault	2	1	Concrete and grates in good condition; minor build up of sediment/debris in bottom of vault.	
6-inch Plug Valve (x2)	3	1	Minor corrosion on valve body and major corrosion on bolts. Functionality of valves is unknown; due to potential risk of damaging valves and age, recommend to replace valves.	
6-inch Check Valve (x2)	3	1	Minor corrosion on valve body and major corrosion on bolts. Due to age, recommend to replace valves.	
Hoist	2	3	Rust on bolts, otherwise in good condition. Portable hoist is unstable.	Consider
Generator	4	3	Existing generator is not efficient and is obsolete; no parts available for repair and finding someone capable of work is difficult. See Photo 2 below.	
Portable Bypass Pump	1	1	-	
Site – yard, fencing, drainage	2	1	Chain-link fencing is in good shape but missing privacy slats. Recently extended and closed back of site due to vandalism of PG&E box	
Access	2	1	Paved, and in good condition. See Photo 3 below.	
Security	1	2	Gate around facility; locks on wet well access hatch, main gate, and structure gate/door. See Photo 3 below.	Consid
Structure	1	1	CMU and roof in good condition. Only repairs over years have been leakproofing, retaining walls also in good shape. Structure does not provide adequate access for generator repairs, clearance from electrical panels.	Consider replacir
Electrical & Instrumentation/Controls	3	2	General maintenance and housekeeping has been performed. Evidence of in-house modifications. No leak alarms, or on/off. Only alarms are high, lag pump, loss of air. All electrical/controls are original. Due to apparent age and modifications, all electrical, instrumentation, and controls assets/systems should be replaced.	
8" Forcemain (1,700 ft)	Not inspected	Not inspected	Replaced 1,600ft of forcemain approx. 10-years ago (asbestos piping); consider additional inspection of forcemain to determine condition.	A Perform condition ass

#### WEST YOST

Recommendations
np capacity should be based on future flow requirements. Consider adding additional (third) pump for backup.
None
ils with standard width the next time major work is completed on pumps and wet well is taken out of service.
None
fy hatch to add safety grate and spring assist opening mechanism.
Replace
None
None
Replace
Replace
onsider installing more robust and permanent hoist.
Replace
None
None
None
Consider installing more secure fencing and gate.
eplacing building to provide adequate clearance and access.
Replace
Assumed to be in acceptable condition.
ion assessment to determine condition and rehabilitation needs.





Photo 1 Lift Station 1 Wet Well

Photo 2 Lift Station 1 Generator



		Table 14. Lift St	ation 2 – Condition Assessment Results and Recommendation	ons
Asset	Condition Rating	Performance Rating	Comments	Recommendations
Overall	-	-	If the District is looking to handover this facility to others for ownership station with a package system (pumps and controls) that vendor can consider alarm package appropriate for resid	maintain; equip with cellular (not dial-up); and
Pump 1	1	1	Recently replaced	None
Pump 2	2	1	Performing fine	None
Pump Guide Rails	2	1	Good shape. Pumps are pulled by hand with a rope.	Install pulley system for pump access.
Check Valve	1	1	Recently replaced	None
1/2-inch Gate Valve (x2)	4	3	Corroded	None
Wet Well	2	1	Serves only 2 homes, takes a while to fill. See Photo 4 below.	None
Wet Well Lid	3	3	Recently DIY fabricated approx. 1 year ago; rusting.	None
Inlet MH	2	1	Rehabbed approx. 10 years ago	None
Outlet MH	4	2	Corrosion on effluent pipe elbow	None
Access	2	4	Dirt path, difficult to access with equipment due to property owner belongings. See Photo 7 below.	Improve site to allow for easier servicing and equipment access.
Security	1	1	Lock on electrical/control box	None
Meter/Control Housing	3	2	Corrosion along inside seals and bottom of box. See Photo 5 below.	None
Meter/Control Cabinet	1	1	In good shape, seals are good and no signs of corrosion. See Photo 5 below.	None
Electrical & Instrumentation/Controls	3	2	Seals on inner panel appear intact and components in acceptable condition. Outer enclosure is in corroded at bottom, potentially due to poor conduit seal from wet well instrumentation. See Photo 5 below. Due to apparent age and modifications, all electrical, instrumentation, and controls assets/systems should be replaced.	Replace. Evaluate conduit and seals from wet well to panel for leakage before re-using.
1.5" Forcemain (130 ft)	Not inspected	Not inspected	Useful life of sewer forcemains is 35-50 years. The forcemain is 48 years old and has no history of repair or rehabilitation.	Replace



Photo 4 Lift Station 2 Wet Well



Photo 5 Lift Station 2 Cabinet



Photo 6 Lift Station 2 Site



Photo 7 Lift Station 2 Si

#### **NEXT STEPS**

This document will be used to understand the District's repair and rehabilitation needs and define the recommendations for the Preliminary Engineer's Report to be completed in a next phase of the project and used to support a construction grant application.

# Attachment A

# Pipeline Database

#### Attachment A. Pipeline Database

<table-container>        Here       Here</table-container>		M	H ID			Pipe Da	ata								PACP Asse	ssment						Final Pipe	eline Action(s)			
No.         No. <th></th> <th>U/S</th> <th>D/S</th> <th></th> <th></th> <th></th> <th>Le</th> <th>ngth</th> <th></th> <th></th> <th></th> <th></th> <th></th> <th></th> <th>F</th> <th>ACP Code and</th> <th>d (Footage)</th> <th></th> <th>O&amp;M</th> <th>Action</th> <th></th> <th></th> <th></th> <th>R</th> <th>&amp;R Action</th> <th></th>		U/S	D/S				Le	ngth							F	ACP Code and	d (Footage)		O&M	Action				R	&R Action	
								ссти			Survey	Structural	O&M	Grade 5	Grade 4	Grade 3	Grade 2	Grade 1	Maint.	Maint.		R&R Reason				
Image: Norme:         Image: N	Pipe ID	ID	ID	Dia	Mtl		GIS	Survey	Need CCTV?	Date	Direction	QR	QR						Needed?	Method			t			Comment
Image: control in the state of the																										
Aless         Solution         Solution <t< td=""><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></t<>																										
Hook, And Mark         Hook	MH 0-1_To_Headworks	MH 0-1	Headworks	12	CI	1976	73	73	N			5100	0000						N		Y	Defect; Unable to be Inspected due to	x			inspected (headworks and DS inaccessible MH) but assumed to be in same poor condition as adjacent
MAX MAX         MAX	MH 5-11A_To_LS-1	MH 5-11A	LS-1	12		1976	29		Y																	
MP2_Ligners         NP3         NP3        NP3         NP3	MH 0-2_To_MH 0-1	MH 0-2	MH 0-1	12	AC	1976	246	246	N	12/5/2023	Downstream	5100	0000	SMW (0)					N		Y	Defect; Unable to be Inspected due to	x			Assume full replacement
Mith Jubid         Mith	MH 0-3_To_MH 0-2	MH 0-3	MH 0-2	12	AC	1976	357	357	N	12/5/2023	Downstream	5100	0000	SMW (0)					N		Y	Defect; Unable to be Inspected due to	x			Assume full replacement
$ \begin{bmatrix} 0 & 0 & 0 & 0 & 0 & 0 & 0 & 0 & 0 & 0$	MH 1-1_To_MH 0-3	MH 1-1	MH 0-3	12	AC	1976	205	205	N	12/5/2023	Downstream	5100	0000	SMW (0)					N		Y	Defect; Unable to be Inspected due to	x			Assume full replacement
Main Dial         Main Dial <t< td=""><td>MH 12-4 To MH 10-1</td><td>MH 12-4</td><td>MH 10-1</td><td>6</td><td>AC</td><td>1976</td><td>285.09523</td><td>270.8</td><td>N</td><td>10/19/2023</td><td>Downstream</td><td>0000</td><td>0000</td><td></td><td></td><td></td><td></td><td></td><td>N</td><td></td><td>N</td><td></td><td></td><td></td><td></td><td></td></t<>	MH 12-4 To MH 10-1	MH 12-4	MH 10-1	6	AC	1976	285.09523	270.8	N	10/19/2023	Downstream	0000	0000						N		N					
Image in the set in t		MH 10-1	MH 10-2	6					N		Downstream	3221						MMC (13.7, 15.1, 226.4) Tap (14.9, 35, 125.5, 146.3,	N		Y			x		consider CIPP. Excavate may cause further
All of a bial bial bial bial bial bial bial bi	MH 10-2 To MH 10-3	MH 10-2	MH 10-3	6	AC	1976	209.32539	206.8	N	10/10/2023	Upstream	4100	0000		B (60.7)			TF (20, 40.4, 181.3)	N		Y				x	
MB191 MB19 MB19         MB192		60 10 1		6					Y						. ,			,				Defect				
Mr 104_10_Mr 105         Mr 105         6         Ac         106         20.8         N         106/200         Developer         4130         000         10         950         300/104         Mr 104         N         1         100/200         100/200         Developer         4130         000         10         950         300/104         Mr 104         N         1         0         1         960/104         300/104         N         1         0         0         N         1         0         0         N         0         N         0         N         0         N         0         N         0         N         0         N         0         N         0         N         0         N         0         N         0         N         0         N         0         N         0         N         0         N         0         N				6	۵C			378		10/10/2023	Downstream	0000	3100			DA7 (233 1)			v	Heavy Cleaning	N					
And the set of the se				6											B (95.9)	JSM (164.4,		TF (12.4, 68.8, 95.5, 151.8,		neuvy cicumig					x	
$ \begin{array}{ c c c c c c c c c c c c c c c c c c c$				6											DAGS (70.6-	JOM (164.4) JOM (17.9)	DAGS (61.2)	MMC (164.4, 166.9) MMC (16.5, 18.4)	Y	Heavy Cleaning	Y	Grade 3+ Structural			x	
Millio, Jo, Millio, Mil															91.7)	91.7)						Delect				
Mm 5 La         Mm 5 A         Mm 6 A	MH 10-7_To_MH 10-6	MH 10-7	MH 10-6	6		1976	221.87566	220.6	N	10/9/2023	Downstream	0000	1100						N		N					
MH 10-6, To, JMH 10-8         MH 10-8         OMH 10-8         OMH 10-9, To, JMH 10-8         OMH 10-1, To,	MH 9-1-A_To_MH 10-7	MH 9-1-A	MH 10-7	6		1976	352.15994	343.7	Ν	10/2/2023	Downstream	4112	0000		JOL(319.3)		FC (167.2)		N		Y				х	
MH 109 Tro, MH 108       M	MH 10-6 To MH 10-8	MH 10-6	MH 10-8	6		1976	133	142.6	N	10/9/2023	Downstream	0000	0000						N		N	belea				erdeks
Image: Condition         Image: Condition<	MH 10-9 To MH 10-8	MH 10-9	MH 10-8	6		1976	171	212 7	N	10/2/2023	Downstream	0000	0000						Y	Root Removal	N					
MH 1-2_To_MH 1-1         MH 1-2         MH 1-1         12         AC         1976         221         N         12/5/203         Downstream         5100         0000         SMW (0)         SMW (0)         N         I         N         I         Grade 3+ Structural Defect; Unable to be Inspected due to Condition         X         Assume full replacement           MH 1-3_To_MH 1-2         MH 1-3         To_MH 1-2         NH 1-3         To_MH 1-2         N         12/5/203         Downstream         5100         0000         SMW (0)         I         I         N         I         Y         Grade 3+ Structural Defect; Unable to Defect; Unable				-															-	Noot Kellioval						
MH 1-2_TO_MH 1-1       MH 1-2       MH 1-2       MH 1-1       12       AC       1976       221       AN       12/5/203       Downstream       5100       0000       SMW (0)       R       R       R       Y       Defect; Unable to be inspected due to Condition       X       Defect; Unable to condition       X       Z       X       Defect; Unable to condition       Defect; Unable to condition       Def	MH 9-1-C_To_MH 10-9	MH 9-1-C	MH 10-9	6		1976	238	207.5	N	10/2/2023	Downstream	0000	0000					TF(136.2)	N		N					
MH 1-3_T0_MH 1-2       MH 1-2       12       AC       1976       388       388       N       12/5/2023       downstream       5100       0000       SMW (0)       N       N       Y       Defect; Unable to be Inspected due to Condition       X	MH 1-2_To_MH 1-1	MH 1-2	MH 1-1	12	AC	1976	221	221	N	12/5/2023	Downstream	5100	0000	SMW (0)					N		Y	Defect; Unable to be Inspected due to	x			Assume full replacement
MH 12-8         MH 12-1         6         AC         1976         122.6         123.         N         10/19/2023         Downstream         0000         0000         M         N         N         M	MH 1-3_To_MH 1-2	MH 1-3	MH 1-2	12	AC	1976	388	388	N	12/5/2023	downstream	5100	0000	SMW (0)					N		Y	Defect; Unable to be Inspected due to	x	_		Assume full replacement
	MH 12-8_To_MH 12-1	MH 12-8	MH 12-1	6	AC	1976	122.6	123	N	10/19/2023	Downstream	0000	0000						N		N					

		МН	ID			Pipe Da	ata								PACP Asse	ssment						Final Pipe	eline Action(s)			
	U/	's	D/S				-	ngth								ACP Code and	d (Footage)		0&M	Action				F	&R Action	
										ССТV														Re	hab	
								ссти		Inspection	Survey	Structural	0&M	Grade 5	Grade 4	Grade 3	Grade 2	Grade 1	Maint.	Maint.	R&R Needed?	R&R Reason	Full Pipe Replacemen			
Pipe ID	10	<b>b</b>	ID	Dia	Mtl	Install Date	GIS	Survey	Need CCTV?	Date	Direction	QR	QR						Needed?	Method			t	CIPP	Spot Repair	Comment
MH 12-1_To_MH 12-2	MH :	12-1	MH 12-2	6	AC	1976	296.70429	286.2	N	10/19/2023	Downstream	3300	2200			JOM (194.7, 196.9, 268.6)	RF (194.7, 196.9)	Tap (105.4, 176.5, 196.1, 269.7) MMC (194.9, 196.9)	N		Y	Grade 3+ Structural Defect		х		2 of Taps are PVC saddles with JOMs and roots; replacing JOMs will address roots. CIPP or?
MH 12-2_To_MH 12-3	MH :	12-2	MH 12-3	6	AC	1976	227.89366	227	N	10/19/2023	Downstream	4132	1100		JOL (227.1)	JOM (95.4) MWLS 50% (226.3-227)		Tap (66.7, 94.1, 182.8) VZ Worm (72.2)	Ν		Y	Grade 3+ Structural Defect			x	Not sure what is going on at R7; needs to be inspected from R7 end
MH 12-5_To_MH 12-3	MH :	12-5	MH 12-3	6	AC	1976	424.71082	419.9	N	10/19/2023	Upstream	4132	0000		B (164.9)	JOM (274.4, 276.6)		Tap (63.3, 144.2, 185.2, 275.4, 286.1, 332.2, 408.4) MMC(274.4 - PVC, 276.6 - AC)	N		Y	Grade 3+ Structural Defect			x	Fix JOM (tap); CIPP for B
MH 12-3_To_MH 12-4	MH :	12-3	MH 12-4	6	AC	1976	255.44777	263.2	N	10/19/2024	Downstream	4100	2100		B (53.1)	MWLS (14.8)	OBZ (74.2)	MWL (19.3, 211.2) Tap (14.8, 16.4, 123.2, 241.5)	Y	Heavy Cleaning (spoon)	Y	Grade 3+ Structural Defect		x		
MH 12-6_To_MH 12-5	MH	12-6	MH 12-5	6	AC	1976	248.99261	239	Ν	10/2/2023	Downstream	3100	0000			JOM (77.5)		MMC (77.5, 79.8) TF (79.8, 85.9, 110.8, 235.4)	Ν		Y	Grade 3+ Structural Defect			x	Excavate & Repair at 77.5 feet
CO 12-1_To_MH 12-6	CO 1	.2-1	MH 12-6	6	PVC	After 1976	179	176.7	N	12/1/2023	Upstream	3122	2100			JOM (39.6)	MWLS 15% (103.1, 140.6)	MWL 5% (107.1) Tap (104.4, 169.1, 171.7)	Ν		Y	Grade 3+ Structural Defect			x	Excavate & Repair at 39.6 ft
MH 12-7_To_MH 12-6	MH :	12-7	MH 12-6	6	AC	1976	325.5189	315.4	N	10/2/2023	Downstream	3100	1100			JOM (289)		TF (35.7, 115.6, 290.7) MMC (289) TS (290.2) RFJ (290.7)	Y	Root Removal	Y	Grade 3+ Structural Defect			x	Excavate & Repair at 289 feet
MH 13-4_To_MH 12-7	MH :	13-4	MH 12-7	6	AC	1976	239.17821	231.9	N	10/2/2023	Downstream	3521	5121	DAR (53.7)		JOM (2.5, 51.5, 97.7, 100.1, 202.9) RMJ (54.4)	MWLS [10%] (33.2) RTJ (151.1)	MMC (2.5, 6.6, 51.5, 203.1, 206.1) TF (4, 5.5, 49.1, 53, 98.9, 104.9, 151.1, 204.7) TFC (110.6) RFJ (47.2, 50)	Y	Root Removal and Heavy Cleaning	Y	Grade 3+ Structural Defect			x	Excavate & Repair at 2.5 and 51.5, 97.7, 100.1 and 202.9 feet.
CO 12-2_To_MH 12-8	CO 1	2-2	MH 12-8	6	PVC	After 1976	288	281.7	N	12/5/2023	Upstream	3121	1100			JOM (16.6)	MWLS 15% (20.3)	MWL 5% (33.8) MWL 15% (67.5) MMC AC (5) Tap (71.3, 74.2, 141.8, 209.8, 251.8, 254.7, 270.7, 273.7, 276.7) RFJ (274.5)	N		Y	Grade 3+ Structural Defect			x	Excavate & Repair at 16.6 ft
MH 13-3_To_MH 12-8	MH	13-3	MH 12-8	6	RCP	1976	303.1	176.3	N	10/19/2023	Downstream	1F00	0000					SCC (entire) Tap (80.3)	N		N					
MH 2-3-A_To_MH 1-3	MH 2	-3-A	MH 1-3	12	CI	1976	272	272	N	12/5/2023	N/A	5100	0000	SMW (0)				τομ (co.s)	N		Y	Grade 3+ Structural Defect; Unable to be Inspected due to Condition	x			Assume full replacement
CO 13-1-A_To_MH 13-			MH 13-1	6		1976	24.5		Y																	
MH 13-1_To_MH 13-1- MH 13-1-B_To_MH 13-1			MH 13-1-C MH 13-1-C	6 6		1976 1976	52.9 55.1		Y Y																	
MH 13-1-C_To_MH 13-	2 MH 13	3-1-C	MH 13-2	6	AC	1976	296.68917	149.5	Ν	10/18/2023	Upstream	2100	4100		MCU (125.3)		MWLS [20%] (106.6)	TFC (132.4)	Ν		Y	Grade 3+ Structural Defect	x			
MH 13-2_To_MH 13-3	MH :	13-2	MH 13-3	6		1976	240.19066	241	Ν	10/18/2023	Downstream	0000	0000					Taps (137, 177)	Ν		N					
CO 13-1-B_To_MH 13-4			MH 13-4	6	AC	1976	288.59028	281.6	N	10/2/2023	Upstream	3100	3111			JOM (28.9) DSZ (139.2)		RFJ (29.4) MMC (29.5, 32.1) TF (30.6, 84.2, 148.8, 203.2, 272.9, 280.4)	Y	Root Removal and Heavy Cleaning	Y	Grade 3+ Structural Defect			x	Excavate & Repair at 28.9 feet.
CO 14-1_To_MH 14-1	CO 1	4-1	MH 14-1	6	+	1976	91		Y									MWL 5% (0)					+ +			
MH 15-2_To_MH 15-1	. МН :	15-2	MH 15-1	6	PVC		341	320.5	N	10/17/2023	Downstream	0000	0000					Tap (106.1) MMC to AC (131) MMC to DIP (140.8) MMC to PVC (274)	N		N					
MH 15-3_To_MH 15-2			MH 15-2	6	PVC	After 1976		282.2	N	11/20/2023	Downstream	3100	0000			MWLS 30% (274- 278)	MWLS 25% (274.9)	MWL 5% (280.1) Tap (2, 233.3)	N		Y	Grade 3+ Structural Defect			x	
MH 15-6_To_MH 15-2 MH 15-4_To_MH 15-3			MH 15-2 MH 15-3	6	PVC PVC	After 1976 After 1976		223.7 256.1	N	11/20/2023 11/20/2023	Downstream Upstream	0000 3322	0000			JOM (16.1) JSM (16.6, 36.5)	MWLS 20% (35.2, 146)	Tap (15.5, 46.1, 190.6) MWL 5% (41, 156.6)	N		N Y	Grade 3+ Structural Defect		х		
MH 15-5_To_MH 15-4	MH	15-5	MH 15-4	6	PVC	After 1976	250	253.4	Ν	11/20/2023	Upstream	0000	0000					Tap (49.4, 95.2)	Ν		Ν					

	MF	1 ID			Pipe Da	ta								PACP Asse	ssment						Final Pipe	line Action(s)	l.		
	U/S	D/S				Ler	ngth							F	PACP Code and	d (Footage)		O&M	Action					R&R Action	
							ссти		CCTV Inspection	Survey	Structural	O&M	Grade 5	Grade 4	Grade 3	Grade 2	Grade 1	Maint.	Maint.	R&R Needed?	R&R Reason	Full Pipe Replacemen	CIPP	ehab Spot Repair	
Pipe ID	ID	ID	Dia	Mti	Install Date	GIS	Survey	Need CCTV?	Date	Direction	QR	QR						Needed?	Method			τ			Comment
CO 15-1_To_MH 15-5	CO 15-1	MH 15-5	6	PVC	After 1976	350	343.4	N	12/4/2023	Upstream	3300	4100			JSM (5.5, 138.5) MWLS 35% (29- 39) MWLS 35-70% (335.4-340 [end])		MWL 5% (159) Tap (128.6, 239.2) MWL 35-70% (335.4-340) MCU (340.3)	N		Y	Grade 3+ Structural Defect		x		Excavate & Repair 29-39ft, and 335-350 ft; CIPP entire pipe
MH 15-7_To_MH 15-6 CO 15-2 To MH 15-7	MH 15-7 CO 15-2	MH 15-6 MH 15-7	8	PVC PVC	After 1976 After 1976		198.7 158.4	N	11/20/2023 11/20/2023	Downstream	0000	0000					Tap (68.6, Tap (55.7, 152.5, 155.9)	N		N					
			0	PVC						Upstream							Tap (91, 121.8, 142.5, 199,								
CO 2-1_To_MH 2-1	CO 2-1	MH 2-1	6		1976	337	312.8	N	10/16/2023	Upstream	0000	0000					203, 223.8, 306.5, 310.5)	Ν		Ν					
MH 2-1_To_MH 2-2	MH 2-1	MH 2-2	6		1976	198	215	N	10/16/2023	Downstream	0000	0000					Tap (88, 183)	N		N	Conde 2: Characterial				
MH 2-2 _To_MH 2-3-A	MH 2-2	MH 2-3-A	6		1976	212	191	N	10/16/2023	Downstream	5100	0000	HSV (188)				Tap (80)	N		Y	Grade 3+ Structural Defect			x	
MH 2-4_To_MH 2-3-A	MH 2-4	MH 2-3-A	12		1976	347	350.1	Ν	12/5/2023	Downstream	5L2L	2100	HSV (105.9) SMW (entire)			OBZ (105.9) SSS (entire)	Tap (25, 105.9, 202.6, 280) ISSR (105.9)	Ν		Y	Grade 3+ Structural Defect	х			
MH 2-8_To_MH 2-3-B	MH 2-8	MH 2-3-B	6	PVC		352	346.7	N	10/17/2023	Downstream	0000	0000						Ν		Ν					
MH 2-5_To_MH 2-4	MH 2-5	MH 2-4	12		1976	331	338.8	N	12/5/2023	Downstream	2L00	2100				DAE (entire) SSS (entire)	Tap (98.2, 155.3, 157.3, 198.7)	Y	Heavy Cleaning	Ŷ	Expected Future Deterioration		x		Likely going to deteriorate like downstream A-Line pipes. Consider heavy cleaning (cleaning may cause failures) and re-CCTV (to veritfy structural integrity, and CIPP), or just full replacement
MH 2-6_To_MH 2-5	MH 2-6	MH 2-5	6		1976	254	244.2	N	10/17/2023	Downstream	0000	0000					Tap(118.8)	Ν		Ν					
MH 3-4_To_MH 2-5	MH 3-4	MH 2-5	12	RCP		275	269.5	N	12/5/2023	Downstream	3100	2100			MWLS 50% (173- 176) MWLS 30% (177- 180)	DAE (entire) MWLS 20% (180 210)		Y	Heavy Cleaning	Ŷ	Grade 3+ Structural Defect, Expected Future Deterioration		x		Likely going to deteriorate like downstream A-Line pipes. Consider heavy cleaning (cleaning may cause failures) and re-CCTV (to veritfy structural integrity, and CIPP), or just full replacement
MH 2-7_To_MH 2-6	MH 2-7	MH 2-6	6		1976	262	252.1	N	10/17/2023	Downstream	3100	0000			JOM(82.9)		Tap (87.3, 238.3)	Ν		Y	Grade 3+ Structural Defect			x	
CO 2-2_To_MH 2-7	CO 2-2	MH 2-7	6		1976	389	364.9	N	10/17/2023	Upstream	4113	0000		JSL(94.7)	JSM (93.3)		MMC (93.3, 94.7), Tap (94, 226, 239.9, 270.4, 287.6, 302.6, 364.9)	Ν		Y	Grade 3+ Structural Defect			x	
MH 2-3-B_To_MH 2-7	MH 2-3-B	MH 2-7	6		1976	234	253.5	N	10/17/2023	Downstream	0000	4100		RBL (2.6)			Tap (2.6, 112.3)	Y	Root Removal	Ν					
MH 15-1_To_MH 2-8	MH 15-1	MH 2-8	6	PVC		272.16	277.3	N	10/17/2023	Downstream	3200	0000			JSM (91.9, 215.5)		Tap (92.5, 255.4)	Ν		Y	Grade 3+ Structural Defect		x		
MH 3-2_To_MH 3-1	MH 3-2	MH 3-1	12	VCP	1976	228	228.2	Ν	12/5/2023	Upstream	0000	0000					MWL 20% (190.1) Tap (61.1)	Ν		Ν					
CO 3-1_To_MH 3-3	CO 3-1	MH 3-3	6		1976	216	205.4	N	10/12/2023	Upstream	3200	0000			JOM (177,181)		MMC (178, 181) TF (178, 179, 192, 203)	N		Y	Grade 3+ Structural Defect			x	
CO 3-2_To_MH 3-3	CO 3-2	MH 3-3	6		1976	290	287.3	N	10/12/2023	Upstream	3400	0000			JOM(38.6), JOM(40.8), JSM(64.8), JOM(79.5)		Tap(40.1, 80.4, 144.2, 151.6, 270.9, 284.7)	N		Y	Grade 3+ Structural Defect	х			
MH 3-1_To_MH 3-4	MH 3-1	MH 3-4	12	VCP	1976	302	24.7	N	12/5/2023	Downstream	0000	0000			,,		Tap /26 E 05 427 0 200 0	Ν		Ν					
MH 3-5_To_MH 3-4	MH 3-5	MH 3-4	8		After 1976	262	257	Ν	11/20/2023	Downstream	0000	0000					Tap (26.5, 85, 127.9, 209.9, 224.2)	Ν		Ν					
CO 3-3_To_MH 3-5	CO 3-3	MH 3-5	8		After 1976	200	198.2	N	11/20/2023	Upstream	3100	0000			JSM (162.5)		Tap (50.9, 142.2, 172.9, 188.3, 189.7, 193.2)	Ν		Y	Grade 3+ Structural Defect		x		
MH 3-3_To_MH 4-2	MH 3-3	MH 4-2	6		1976	200	190	Ν	10/12/2023	Downstream	3121	0000			JSM (52)	MWLS 20% (96)	Tap (183)	N		Y	Grade 3+ Structural Defect			x	
MH 4-1_To_MH 4-2 MH 4-2_To_MH 4-3	MH 4-1 MH 4-2	MH 4-2 MH 4-3	6		1976 1976	74.09164 231	59 240.2	N N	10/12/2023 10/12/2023	Upstream Downstream	0000	0000						N N		N N					
MH 4-8_T0_MH 4-3	MH 4-2 MH 4-8	MH 4-3	6		1976	385	355.3	N	10/12/2023	Upstream	0000	0000					Tap (76.4, 100.2, 231.2, 251.7, 351)	N		N					
CO 4-1_To_MH 4-4	CO 4-1	MH 4-4	6	AC	1976	253	236.5	N	10/16/2024	Upstream	3200	0000			JOM (7.8) JSM (95.6)		MWL 5% (0) Tap (94.5, 122.2, 231.2, 233, 234.6)	Ν		Y	Grade 3+ Structural Defect			x	
MH 4-3_To_MH 4-4	MH 4-3	MH 4-4	6		1976	374	383	N	10/12/2023	Downstream	3100	0000			JOM (63)		Tap (70, 269)	N		Y	Grade 3+ Structural Defect			x	
MH 4-4_To_MH 4-5	MH 4-4	MH 4-5	6		1976	168	167	N	10/16/2023	Downstream	2100	0000				MWLS 15% (132)		Ν		Ν					

#### Attachment A. Pipeline Database

	MI	1 ID			Pipe Da	ita								PACP Asses	sment						Final Pipe	line Action(s)			
	U/S	D/S				Lei	ngth							Р	ACP Code and	l (Footage)		0&0	/ Action				R	&R Action	
									ссти														Reł	ab	
							ссту		Inspection	Survey	Structural	O&M	Grade 5	Grade 4	Grade 3	Grade 2	Grade 1	Maint.	Maint.	R&R	R&R Reason	Full Pipe			
					Install				inspection	Survey	Structural	ORIVI	Grade 5	Grade 4	Grade 5	Glade 2	Glade 1	want.	Ividinit.	Needed?		Replacemen t	CIPP	Spot Repair	
Pipe ID	ID	ID	Dia	Mtl	Date	GIS	Survey	Need CCTV?	Date	Direction	QR	QR						Needed?	Method			-			Comment
CO 4-2_To_MH 4-7 CO 14-2_To_MH 4-8	CO 4-2 CO 14-2	MH 4-7 MH 4-8	6		1976	347		Y Y																	
MH 14-1_To_MH 4-9	MH 14-1	MH 4-9	6		1976	171		Ŷ																	
																RFJ(150.4), JOM									
MH 5-12_To_MH 5-1	MH 5-12	MH 5-1	6		1976	174	250.9	N	10/10/2023	Downstream	4133	2311		JSL(244.1)	JSM(178), JOM (243.9), JOM (246)		Tap (81.3, 177, 245.3), RFJ (176.5), MMC (178, 243.9, 246)	Y	Root Removal	Y	Grade 3+ Structural Defect			x	
																(246)									
MH 5-9_To_MH 5-10	MH 5-9	MH 5-10	12		1976	118		Y																	
MH 5-10_To_MH 5-11	MH 5-10	MH 5-11	12		1976	313		Y			-														
MH 4-5_To_MH 5-11-A	MH 4-5	MH 5-11-A	6		1976	403	368.8	N	10/16/2023	Downstream	3100	0000			JSM(367)		MMC (89.1, 89.3, 367), Tap (89.3, 367.8), MGO(269.9)	Ν		Y	Grade 3+ Structural Defect			x	
MH 5-11_To_MH 5-11-A	MH 5-11	MH 5-11-A	12		1976	330		Y																	
CO 5-3_To_MH 5-12	CO 5-3	MH 5-12	6		After 1976	234	239.9	N	12/4/2023	Upstream	0000	0000					Tap (41.9, 43.2, 48.5, 115.9, 179, 197, 238.2, 239.9)	Ν		N					
CO 5-6_To_MH 5-2	CO 5-6	MH 5-2	6			60	56.2	N	12/1/2023	Upstream	0000	0000					Tap (2, 36, 55.9)	N		N					
			Ť	1	1	50			, -, 2020	- periodin		- 300	1			1	T (50 T 05 4)								
MH 5-1_To_MH 5-2	MH 5-1	MH 5-2	6	AC	1976	203	207.1	Ν	12/1/2023	Downstream	3300	2200			JOM (51.8, 82.3, 202.6)	OBZ (53.6, 84.2)	Tap (58.7, 85.1) MMC to PVC (51.8, 82.3) MMC to AC (53.6)	Y		Y	Grade 3+ Structural Defect			х	
MH 5-2_To_MH 5-3	MH 5-2	MH 5-3	6		1976	183		Y																	
MH 5-3_To_MH 5-4	MH 5-3	MH 5-4	6		1976	175	184.2	N	10/11/2023	Upstream	0000	0000					TF(10.6, 86.6, 146.8, 177.2), TS(172.7)	Ν		N					
MH 5-5_To_MH 5-4	MH 5-5	MH 5-4	6		1976	253	240.4	N	10/11/2023	Downstream	3300	0000			JOM (111.1, 145.1), JSM(156.8)		TF(49.9, 112.8, 119.7, 146.2, 160.1,199.0), TFC(150.3), MMC (111.7, 113.4, 146.9,	N		Y	Grade 3+ Structural Defect			x	
CO 5-2_To_MH 5-5	CO 5-2	MH 5-5	6		1976	247	243	N	10/11/2023	Upstream	0000	4100		RBJ (243)	3500(150.0)		198.0, 199.8), Tap (112.3, 174.5, 178.3, 242.3)	Y	Root Removal	N					
			-		1570		2.15		10, 11, 2020	opsicum		1100					MSA (243)								
MH 5-6_To_MH 5-5	MH 5-6	MH 5-5	6		1976	417	412.1	Ν	10/11/2023	Upstream	3100	4100		DAZ(411.7) Concrete in pipe with block about 25%	JSM (23.9)		TF(128.9, 218.5, 347.2)	Y	Heavy Cleaning	Y	Grade 3+ Structural Defect			х	
CO 5-7_To_MH 5-6	CO 5-7	MH 5-6	6		1976	113	108.9	N	10/11/2023	Upstream	0000	4100		RBL (108.9)			MWL 5% (0)	Y	Root Removal	N					4 ft not inspected
 MH 4-9_ToMH 5-6	MH 4-9	MH 5-6	6		1976	382		Y		•				. ,			Tap (108.9)								
MH 5-4_To_MH 5-7	MH 5-4	MH 5-7	6		1976	370	359.6	N	10/11/2023	Downstream	3212	0000			JOM (193.2, 357.7)	CL(29.7)	TF(83.9, 94.5, 124.2, 165.2, 175.9, 181.5, 192.4, 196.5, 256.2, 273.3, 323.2), MMC (357.7)	Ν		Y	Grade 3+ Structural Defect			x	
MH 6-2 To MH 5-7	MH 6-2	MH 5-7	12		1976	365		Y																	
CO 5-4_To_MH 5-8	CO 5-4	MH 5-8	6		1976	331	322.4	N	10/11/2023	Upstream	4100	2200		B (319.2)		RTJ (319.2)	TF (72.4, 226.7, 276.6, 316.8, 319.6), TS (98.2), MMC (318.8, 320.5), RFL	Y	Root Removal	Y	Grade 3+ Structural Defect			x	
MH 5-7_To_MH 5-9	MH 5-7	MH 5-9	12	+	1976	257		Y									(98.2)								
MH 5-8_To_MH 5-9	MH 5-8	MH 5-9	6		1976	175	174.7	N	10/11/2023	Downstream	4100	0000		B(5.5)			Tap(4.5, 74.8, 118.5, 140.9, 173.8), MMC(120.7, 172.8)	N		Y	Grade 3+ Structural Defect			x	
MH 5-9-A_To_MH 5-9	MH 5-9-A	MH 5-9	6		1976	337	326.9	N	10/11/2023	Upstream	0000	0000					MWL(9.5), Tap(122.3,	N		N	Derett				
									,, 2020								192.1), MMC(320.4)								
CO 6-10-A_To_MH 6-10	CO 6-10-A	MH 6-10	6	-		33		Y								MWLS 25% (99-	· Tap (11.7, 32.6, 165.1,								ould consider spot repairs
MH 6-11_To_MH 6-10	MH 6-11	MH 6-10	8	PVC	After 1976	342	340.5	N	12/4/2023	Downstream	2300	0000				150, 335)	307.1)	Ν		N				U	ould consider spot repairs for minor sags
CO 6-10-A_To_MH 6-10	CO 6-10-A	MH 6-10	6		1976	33		Y								,									<u> </u>
MH 6-12_To_MH 6-11	MH 6-12	MH 6-11	8	PVC	After 1976	339	345.5	N	11/21/2023	Downstream	2300	0000				MWLS 15% (100.3) JOS (99.2) SSS (302-340)	Tap (95.1, 101.5, 102.7, 139.5, 251.9) MMC DIP (304.1) MMC PVC (340.1)	Ν		N				с	onsider lining or replacing CIP section
CO 6-3_To_MH 6-12	CO 6-3	MH 6-12	8		After 1976	220	210.9	N	11/21/2023	Downstream	0000	0000					Tap (5.5, 57.5, 204.3, 210.9)	Ν		N					
CO 7-2_To_MH 6-1	CO 7-2	MH 6-1	6	AC	1976	253.0413	246.7	N	9/27/2023	Upstream	3300	5131	RMB (84-90.8)		JSM (22) RML (90.8) JOM (154, 238.9)		RFJ (22, 53.5, 91.5) TF (23.8, 84, 91.5, 157.4, 177.9, 224.1, 240.9, 242.8, 244.9)	Y	Root Removal	Y	Grade 3+ Structural Defect			x	

#### Attachment A. Pipeline Database

	MH	1 ID			Pipe Da	ata								PACP Asses	ssment						Final Pipe	line Action(s)			
	U/S	D/S				-	ngth								ACP Code and	d (Footage)		0&M	Action					&R Action	
	•						ссту		CCTV Inspection	Survey	Structural	O&M	Grade 5	Grade 4	Grade 3	Grade 2	Grade 1	Maint.	Maint.	R&R Needed?	R&R Reason	Full Pipe Replacemen		hab	
Pipe ID	ID	ID	Dia	Mtl	Install Date	GIS	Survey	Need CCTV?	Date	Direction	QR	QR						Needed?	Method			t	CIPP	Spot Repair	Comment
MH 6-1_To_MH 6-2 MH 6-3 To_MH 6-2	MH 6-1 MH 6-3	MH 6-2	6		1976	372	369.1	N	9/27/2023	Downstream	3600	5100	DSGV (271.7) 35%		JSM(92.2), JOM (114.9, 139.7, 219.1, 273.3, 335.8)		TF(89, 91, 117, 129.3, 142.2, 169.6, 196.2, 215.2, 220.8, 271.6, 275.2, 303.7, 337.5), MMC (89.7, 92.2, 115.7, 118.9, 139.7, 143.1, 167.9, 170.9, 194.8, 197.4, 221.8, 247.3, 250.1, 273.3, 276.3, 302.4, 304.7, 335.8, 337.7)	Ŷ	Heavy Cleaning	Y	Grade 3+ Structural Defect	x			
MH 6-3_10_MH 6-2 MH 6-4 To MH 6-3	MH 6-3 MH 6-4	MH 6-2 MH 6-3	12 8		1976 1976	230 163	174	Y N	10/9/2023	Downstream	0000	0000					Tap (143)	N		Ν					
MH 6-8_To_MH 6-3	MH 6-8	MH 6-3	6		After 1976		300.3	N	11/17/2023	Downstream	0000	0000					Tap (28.6, 111.5)	N		N					
MH 6-5_To_MH 6-4	MH 6-5	MH 6-4	8	AC	1976	400	403	Ν	10/9/2023	Downstream	3100	0000			JSM (107)		Tap (93,109, 201, 243, 310, 325, MMC (324 to 326 - PVC)	Ν		Y	Grade 3+ Structural Defect			x	
MH 7-8_To_MH 6-4	MH 7-8	MH 6-4	6		1976	195	185.1	Ν	9/27/2023	Downstream	0000	0000					WINC (524 to 520 1 VC)	N		Ν					
MH 6-6 To MH 6-5	MH 6-6	MH 6-5	8		1976	189	186.4	N	10/9/2023	Downstream	0000	0000					MWL(0), MGP(12.2),	N		N				[ İ _	
MH 6-7_To_MH 6-6	MH 6-7	MH 6-6	6		1976	409	404.5	N	9/26/2023	Downstream	0000	3100			DSZ (71.5)		Tap(85.5, 97.3) MWL( 55.8), Tap(79.1,127.5,154.9,175.5, 246.8,263.6, 276.5, 317), MGP(13.4,14.8,37,131.5,215 .6, 395.5)	Ŷ	Heavy Cleaning	N					
MH 7-10_To_MH 6-6	MH 7-10	MH 6-6	6	AC	1976	374	362	N	11/9/2023	Downstream	3500	0000			<u>JOM (83, 162, 269, 360)</u> JSM (210)		Tap (103, 137, 150, 246, 342, 360) MMC (341 to 343 - PVC saddle for tap) MMC (360 to 362 - PVC saddle for tap)	Ν		Y	Grade 3+ Structural Defect			x	
CO 6-1_To_MH 6-7	CO 6-1	MH 6-7	6		1976	227	223.4	Ν	9/26/2023	Upstream	4112	0000		B(5.9)		MWLS(204.9)	Tap(104.7, 183.8, 204.1, 205, 206.4, 216.2, 220.5), MMC (203.8)	Ν		Y	Grade 3+ Structural Defect			×	
MH 7-12_To_MH 6-7	MH 7-12	MH 6-7	6		1976	365	356.3	N	9/26/2023	Upstream	4133	0000		B(181.2)	JSM(151.4), JOM (180.9, 356.3)		Tap (81.3, 98.4, 156, 167.7, 218.7, 275.4, 318.1, 356.3), MMC(274.5, 277.4)	Ν		Y	Grade 3+ Structural Defect			x	
MH 8-1_To_MH 6-7	MH 8-1	MH 6-7	6	AC	1976	440	310	N	9/25/2023	Upstream	5143	0000	MWLS 50-75%+ (at MH-F14)	B (2, 265) JSL (291)	OBM 15% (105) JOM (214) JSM (238, 240)		MWLS 25% (10) Tap (98, 122, 162, 208, 209, 213, 222, 265, 284) MMC (208 to 210 - PVC) MMC (213 to 215 - PVC) MMC (265 to 267 - PVC) MMC (291 to MSA - PVC)	Ν		Y	Grade 3+ Structural Defect	x			
MH 6-8-A_To_MH 6-8	MH 6-8-A	MH 6-8	6	PVC	After 1976	140	129.3	N	11/17/2023	Downstream	0000	0000					Tap (5.4, 103.1)	Ν		Ν					
MH 6-8-B_To_MH 6-8-A	MH 6-8-B	MH 6-8-A	8	-	After 1976		70.6	N	11/17/2023	Downstream	0000	0000					Ten (C4 4 30 5 60 0)	N		N				T	
MH 6-8-C_To_MH 6-8-B MH 6-8-G_To_MH 6-8-B	MH 6-8-C MH 6-8-G	MH 6-8-B MH 6-8-B	-	PVC PVC	After 1976 After 1976		99.7 212.8	N N	11/17/2023 11/17/2023	Upstream Upstream	0000	0000	+				Tap (61.4, 70.7, 90.6) Tap Capped (174.5)	N		N				<u>├</u>	
CO 6-8-D_To_MH 6-8-C	CO 6-8-D	MH 6-8-C	8		After 1976			Y	, _ , _ 020												<u> </u>			<u> </u>	
CO 6-8-F_To_MH 6-8-G	CO 6-8-F	MH 6-8-G		PVC	After 1976		87.3	N	11/17/2023	Upstream	0000	0000					Tap (57.5, 73.4, 84.5)	N	]	N				ļŢ	
MH 6-10_To_MH 6-9	MH 6-10	MH 6-9	8		After 1976	120	120.8	N	12/4/2023	Downstream	0000	0000	+				MWL 10% (26.7)	Ν		N				<u>├</u> ───┤	
MH 7-9_To_MH 7-10	MH 7-9	MH 7-10	6		1976	339	335.2	N	10/9/2023	Downstream	0000	0000					TF(23.6, 103.2, 128.9, 231.3, 277.8, 320.9), RPL(329.2)	Ν		Ν					
CO 7-8_To_MH 7-11	CO 7-8	MH 7-11	6		1976	162	164.9	Ν	9/26/2023	Upstream	4123	0000		B(25.4)	JOM(24.3), JSM(24.7)		TF(25.9, 93.1, 162.4), RFJ(26.7)	Ν		Y	Grade 3+ Structural Defect			х	
CO 7-7_To_MH 7-12	CO 7-7	MH 7-12	6		1976	218	213.3	N	9/26/2023	Upstream	3100	0000			JOM (133.6)		TF(93, 158.6, 169.4, 173.1, 187, 208.3, 211.1)	Ν		Y	Grade 3+ Structural Defect			х	
MH 7-11_To_MH 7-12	MH 7-11	MH 7-12	6	L	1976	183	175.3	N	9/26/2023	Upstream	0000	0000					TF (53, 138.9)	Ν		Ν				<u>                                      </u>	
CO 10-2_To_MH 7-12-A	CO 10-2	MH 7-12-A	6	_	1976	4.1		Y				-													
CO 10-2-A_To_MH 7-12-A	CO 10-2-A	MH 7-12-A	6		1976	15.3		Y					+				+							<b>├</b> ───┤	
MH 7-13A_To_MH 7-13 CO 7-4_To_MH 7-14	MH 7-13A CO 7-4	MH 7-13 MH 7-14	6		1976 1976	172.7 35		Y Y									+							├	
MH 7-13_To_MH 7-14	MH 7-13	MH 7-14 MH 7-14	6		1976	237		Y					1						<u>                                     </u>						
CO-19_To_MH 7-2	CO-19	MH 7-2	6		1976	325	270.6	N	10/10/2023	Upstream	0000	0000						N		N				1	
MH 7-2_To_MH 7-3	MH 7-2	MH 7-3	6		1976	113	104.6	N	9/26/2023	Downstream	0000	0000					TF(32.6)	N		N					

	Mł	1 ID		Pipe	Data								PACP Asse	ssment						Final Pipe	eline Action(s)			
	U/S	D/S			Le	ngth							I	ACP Code and	d (Footage)		0&N	I Action				I	R&R Action	
				Install		ссти		CCTV Inspection	Survey	Structural	O&M	Grade 5	Grade 4	Grade 3	Grade 2	Grade 1	Maint.	Maint.	R&R Needed?	R&R Reason	Full Pipe Replacemen t	Re CIPP	hab Spot Repair	
Pipe ID	ID	ID	Dia	Mtl Date	GIS	Survey	Need CCTV?	Date	Direction	QR	QR						Needed?	Method						Comment
CO 7-9_To_MH 7-4	CO 7-9	MH 7-4	6	After 197		95.2	N	12/1/2023	Downstream	3200	0000			JOM (12.6, 63)		MWL 5% (14.2) Tap (75.4, 78.6, 81.5, 87.5)	N		Y	Grade 3+ Structural Defect		х		
MH 7-14_To_MH 7-4	MH 7-14	MH 7-4	6	1976	196	194.1	N	9/26/2023	Upstream	0000	0000					TF(74.2) TF(11.9, 16, 26.8, 40.5, 71,	N		N					
MH 7-3_To_MH 7-4	MH 7-3	MH 7-4	6	1976	227	219.4	N	9/26/2023	Downstream	0000	0000				FC (215.3)	146, 162.1) TF (79.9, 90.8, 127.4, 211.4,	N		N					
CO 7-1_To_MH 7-5	CO 7-1	MH 7-5	6	1976	285	275.8	N	9/27/2023	Upstream	5133	0000	HSV (215.6)		JOM(0, 3, 210.1)		252.5, 273.2), MMC(210.1, 213.2)	N		Y	Grade 3+ Structural Defect			x	
MH 7-4_To_MH 7-5	MH 7-4	MH 7-5	6	1976	173	158.6	Ν	9/26/2023	Upstream	5114	0000	JOL(158.6)	JOM(156.9)	JSM(72.4)		TF(71.8, 88.9)	N		Y	Grade 3+ Structural Defect			x	
MH 7-6_To_MH 7-5	MH 7-6	MH 7-5	6	1976	118	116.4	N	9/27/2023	Downstream	0000	0000					MWL(16.4)	N		N					
CO 7-5_To_MH 7-6	CO 7-5	MH 7-6	6	1976	180	177.4	Ν	9/27/2023	Upstream	4143	0000		JSL(21.7)	JOM(15.9, 156.8, 164.4), JSM (161.7)		MMC(15.9, 21.7), TF(17.4, 70.2 123.3, 126.5, 162.8, 174.1)	N		Y	Grade 3+ Structural Defect	×			
CO 7-3_To_MH 7-7	CO 7-3	MH 7-7	6	AC After 197	6 120	123.4	N	12/1/2023	Upstream	3100	0000			JOM (37.3)		Tap (48.3, 79.8, 121.3)	N		Y	Grade 3+ Structural Defect		х		
MH 7-5_To_MH 7-7	MH 7-5	MH 7-7	6	1976	363	356.9	N	9/27/2023	Downstream	3132	0000			JOM(342.7)	CC(2, 127.8), IS(2)	TF(76.7, 136.8)	N		Y	Grade 3+ Structural Defect			x	
CO 7-6_To_MH 7-8	CO 7-6	MH 7-8	6	1976	266	263.1	N	9/27/2023	Upstream	0000	0000					TF(43.6, 93.7, 143.8, 204.3, 215.1, 206.6), MMC (215.1,	N		N					
MH 7-7_To_MH 7-8	MH 7-7	MH 7-8	6	1976	50	45.5	N	10/10/2023	Downstream	3100	0000			JSM(5.6)		216.8)	N		Y	Grade 3+ Structural Defect			x	
MH 10-8 To MH 7-9	MH 10-8	MH 7-9	6	1976	324	307.8	N	10/9/2023	Downstream	0000	0000					TF(280.5)	N		N					
CO 8-3_To_MH 8-1	CO 8-3	MH 8-1	6	1976	431	335.3	N	9/25/2023	Upstream	4143	0000		JOL(50.9)	JSM(51.7, 178.4), JOM(331.7, 335.3)	MWLS (332.9)	Tap (51.1, 85.6, 145.4,	N		Y	Grade 3+ Structural Defect	x			100 ft not inspected due to offset couldn't pass
MH 8-2_To_MH 8-1	MH 8-2	MH 8-1	6	AC 1976	369	361.6	N	9/25/2023	Upstream	3200	0000			JSM(6.2, 136.7)		TF(65.6, 134.1, 136.1, 154.9, 214.1, 255.1), MMC(134, 136.7)	N		Y	Grade 3+ Structural Defect			x	
MH 9-2_To_MH 9-1-C	MH 9-2	MH 9-1-C	6	1976	335	341	N	10/2/2023	Upstream	0000	0000					Tap (15, 75, 135, 192, 333)	N		N					
CO 8-2_To_MH 8-2	CO 8-2	MH 8-2	6	1976	435	414.6	N	9/25/2023	Upstream	4133	0000		JOL(413.2)	JOM(0.3, 150.7, 326.3)		TF(0.3, 7.1, 143, 148.9, 167.2, 178.6, 195.3, 257.2, 309.7, 325.6, 391.5), MMC (140.9, 150.7, 413.2)	N		Y	Grade 3+ Structural Defect	x			
MH 8-4_To_MH 8-2	MH 8-4	MH 8-2	6	AC 1976	25	2.6	N	9/25/2023	Upstream	4100	0000		JOL (2)			MWL 5% (0) MMC to AC (2) MSA (2.6)	Ν		Y	Grade 3+ Structural Defect	x			loint offset at PVC segment
CO 8-4_To_MH 8-3	CO 8-4	MH 8-3	6	After 197	6 178	154.3	Ν	11/17/2023	Downstream	2R00	0000			SSS (0-96) DAZ (entire length at bottom)		Tap (72.6, 131.4, 154.3 (x2)) MMC PVC (153.7)	Y	Heavy Cleaning	Y	Grade 3+ Structural Defect		x		CIPP for spalling after heavy cleaning
CO 9-4_To_MH 8-4	CO 9-4	MH 8-4	8	PVC After 197	6 138	139.9	N	11/21/2023	Upstream	3100	0000				JSS (101)	Tap (41.8, 136.3, 138)	N		Ν					
MH 8-5_T0_MH 8-4	MH 8-5	MH 8-4	6	PVC/AC 1976	256	254.4	N	9/25/2023	Upstream	4100	0000		JOL (1)			MWL 5% (0) Tap (53.7, 69.6, 77.1, 125.3, 144.9) MMC to AC (1) MMC to PVC (148.6)	N		Y	Grade 3+ Structural Defect			x	
CO 8-1_To_MH 8-5	CO 8-1	MH 8-5	6	PVC 1976	212	205	N	11/21/2023	Upstream	0000	0000					Tap (35.2, 135.5, 190.7, 198.6)	N		N					
MH 9-1-B_To_MH 9-1-A	MH 9-1-B	MH 9-1-A	6	1976	149.80259	148.4	N	10/2/2023	Upstream	0000	0000					TF(19.6, 36.7, 96.6, 146.7)	N		N					
MH 9-3_To_MH 9-2	MH 9-3	MH 9-2	6	1976	290	91	N	10/2/2023		4100	0000		JOL (91)			Tap (90.7)	N		Y					MSA Unknown; need rest of line
MH 9-4_To_MH 9-3	MH 9-4	MH 9-3	6	AC 1976	248.37807		N	10/2/2023	Upstream	3300	1400			JOM (72.7, 74.8, 249.4)		TF (4, 74.1) MMC (72.8, 74.8) RFJ (74.8) DAGS (60-71)	Y	Root Removal and Heavy Cleaning	Y	Grade 3+ Structural Defect			x	
CO 9-3_To_MH 9-4	CO 9-3	MH 9-4	6	AC 1976	136.53632	128.4	Ν	12/1/2023	Upstream	0000	0000					Tap (96.6, 123.5)	N		N					

# Attachment B

### Manhole Database

#### Attachment B. Manhole Database

Facility ID	Inspection Status	CoverCondition	Frame Condition	Chimney Condition	Cone Condition	Wall Condition	Bench Condition	Channel Condition	Count of Infiltration Staining	Count of Defective + Corroded	Replace or Rehabilitation?
Facility ID MH 0-3	Complete	Cover Condition Sound	Frame Condition Sound	Chimney Condition Defective	Cone Condition NA - No Cone	Wall Condition Defective	Bench Condition Defective	Channel Condition Defective	Observations 0	+ Corroded 4	Replace
MH 10-1	Complete	Sound	Sound	Sound	NA - No Cone	Sound	Sound	Sound	0	0	
MH 10-2 MH 10-3	Complete	Sound	Sound	Sound	Sound	Sound	Sound Sound	Sound Sound	1	0	
MH 10-3	Complete Complete	Sound Sound	Sound Sound	Sound Sound	Sound Sound	Sound Sound	Sound	Sound	1	0	
MH 10-5	Complete	Sound	Sound	NA - No Chimney	NA - No Cone	Sound	Sound	Sound	1	0	
MH 10-6	Complete	Sound	Sound	Sound	Sound	Sound	Sound	Sound	1	0	
MH 10-7 MH 10-8	Complete Complete	Sound Sound	Sound Sound	Sound Sound	Sound NA - No Cone	Sound Sound	Sound Sound	Sound Sound	1	0	
MH 10-9	Complete	Sound	Sound	Sound	Sound	Sound	Sound	Sound	1	0	
MH 12-1	Complete	Sound	Sound	Sound	NA - No Cone	Sound	Sound	Sound	1	0	
MH 12-2 MH 12-3	Complete Complete	Sound Sound	Sound Sound	Sound NA - No Chimney	NA - No Cone NA - No Cone	Sound Sound	Sound Sound	Sound Sound	1 0	0	
MH 12-3 MH 12-4	Complete	Sound	Sound	Defective	Sound	Sound	Sound	Sound	1	1	
MH 12-5	Complete	Sound	Sound	Sound	Sound	Sound	Sound	Sound	1	0	
MH 12-6	Complete	Sound	Sound	Sound	NA - No Cone	Sound	Sound	Sound	1	0	
MH 12-7 MH 12-8	Complete Complete	Sound Sound	Sound Sound	Sound NA - No Chimney	Sound NA - No Cone	Sound Sound	Sound NA - No Bench	Sound NA - No Channel	1 0	0	
MH 1-3	Complete	Sound	Sound	Defective	Defective	Defective	Defective	Defective	1	5	Replace
MH 13-1	Complete	Sound	Sound	Defective	Defective	Sound	Sound	Sound	1	2	
MH 13-1-C	Complete	Sound	Sound	Sound	NA - No Cone	Sound	Sound	Sound	1 0	0	
MH 13-2 MH 13-3	Complete Complete	Sound Sound	Sound Sound	Sound Sound	Sound Sound	Sound Sound	Sound Sound	Sound Sound	1	0	
MH 13-4	Complete	Sound	Sound	Sound	Sound	Sound	Sound	Sound	1	0	
MH 15-2	Complete	Sound	Sound	Sound	Sound	Sound	Sound	Sound	0	0	
MH 15-4	Complete	Sound	Sound	Sound	Sound	Sound	Sound	Sound	0	0	
MH 15-6 MH 15-7	Complete Complete	Sound Sound	Sound Sound	Sound Sound	Sound Sound	Sound Sound	Sound Sound	Sound Sound	0	0	
MH 2-1	Complete	Sound	Sound	Sound	NA - No Cone	Sound	Sound	NA - No Channel	1	0	
MH 2-2	Complete	Sound	Sound	Sound	Sound	Sound	Sound	NA - No Channel	0	0	
MH 2-3-A	Complete	Sound	Sound	Sound	Sound	Sound	Defective	NA - No Channel	1	1	
MH 2-3-B MH 2-4	Complete Complete	Sound Corroded	Sound Corroded	Defective Sound	Sound NA - No Cone	Sound Defective	Sound Defective	Sound NA - No Channel	1	1 4	Replace
MH 2-5	Complete	Sound	Sound	Defective	NA - No Cone	Defective	Defective	Defective	1	4	Replace
MH 2-6	Complete	Sound	Sound	Defective	Sound	Sound	Sound	NA - No Channel	0	1	
MH 2-7	Complete	Sound	Sound	Defective	NA - No Cone	Sound	Sound	NA - No Channel	0	1	Devile
MH 3-1 MH 3-2	Complete Complete	Corroded Corroded	Corroded Corroded	Defective Defective	Defective NA - No Cone	Defective Sound	Defective Sound	NA - No Channel Sound	1	6	Replace Rehabiliation
MH 3-3	Complete	Sound	Sound	Sound	NA - No Cone	Sound	Sound	NA - No Channel	1	0	Reliabiliation
MH 3-4	Complete	Sound	Sound	Defective	NA - No Cone	Defective	Defective	Defective	1	4	Replace
MH 3-5	Complete	Sound	Sound	Sound	Sound	Sound	Sound	Sound	0	0	
MH 4-1 MH 4-2	Complete Complete	Sound Corroded	Sound Corroded	Sound Sound	NA - No Cone Sound	Sound Sound	Sound NA - No Bench	Sound NA - No Channel	0	0	
MH 4-3	Complete	Sound	Sound	Sound	Sound	Sound	Sound	Sound	0	0	
MH 4-4	Complete	Sound	Corroded	NA - No Chimney	NA - No Cone	Sound	Sound	Sound	0	1	
MH 4-5	Complete	Corroded	Corroded	Sound	Sound	Sound	Sound	Sound	1	2	
MH 4-8 MH 5-1	Complete Complete	Sound Sound	Sound Sound	Sound Sound	Sound Sound	Sound Sound	Sound Sound	Sound Sound	1 2	0	
MH 5-10	Complete	Corroded	Corroded	Sound	Sound	Sound	Sound	Sound	0	2	
MH 5-11-A	Complete	Corroded	Corroded	Sound	Sound	Sound	Sound	Sound	3	2	
MH 5-12	Complete	Sound	Sound	Sound	Sound	Sound	Sound	Sound	0	0	
MH 5-12 MH 5-2	Complete Complete	Sound Sound	Sound Sound	Sound Sound	NA - No Cone Sound	Sound Sound	Sound Sound	Sound Defective	1 0	0	
MH 5-4	Complete	Sound	Sound	Sound	Sound	Sound	Sound	Sound	0	0	
MH 5-5	Complete	Corroded	Corroded	Sound	Sound	Sound	Sound	Sound	0	2	
MH 5-6	Complete	Sound	Sound	Defective	Sound	Sound	Sound	Sound	1	1	
MH 5-7 MH 5-8	Complete Complete	Sound Sound	Sound Sound	Sound Sound	Sound Sound	Sound Sound	Sound Sound	Sound Sound	0	0	
MH 5-9	Complete	Corroded	Corroded	Defective	Sound	Sound	Sound	Sound	0	3	Rehabiliation
MH 5-9-A	Complete	Sound	Sound	Sound	Sound	Sound	Sound	Sound	0	0	
MH 6-1	Complete	Sound	Sound	Sound	Sound	Sound	Sound	Sound	1	0	
MH 6-11	Complete	Sound	Sound	Sound Sound	Sound	Sound Sound	Sound	Sound	0	0	
MH 6-12 MH 6-2	Complete Complete	Sound Sound	Sound Sound	Sound	Sound	Sound	Sound Sound	Sound	0	0	
MH 6-3	Complete	Sound	Sound	Sound	Sound	Sound	Sound	Sound	0	0	
MH 6-4	Complete	Sound	Sound	Sound	Sound	Sound	Sound	Sound	0	0	
MH 6-5 MH 6-6	Complete Complete	Sound Sound	Sound Sound	Sound Sound	Sound Sound	Sound Sound	Sound Sound	Sound Sound	1 0	0	
MH 6-6 MH 6-7	Complete	Sound	Sound	Sound	Sound	Sound	Sound	Defective	0	1	
MH 6-8	Complete	Sound	Sound	Sound	Sound	Sound	Sound	Sound	0	0	
MH 6-8-A	Complete	Sound	Sound	Sound	Sound	Sound	Sound	Sound	0	0	
MH 6-8-B MH 6-8-C	Complete Complete	Sound Sound	Sound Sound	Sound Sound	Sound Sound	Sound Sound	Sound Sound	Sound	0	0	
MH 6-8-F	Complete	Sound	Sound	Sound	Sound	Sound	Sound	Sound	0	0	
MH 6-8-G	Complete	Sound	Sound	Sound	Sound	Sound	Sound	Sound	0	0	
MH 6-9	Complete	Sound	Sound	NA - No Chimney	NA - No Cone	Sound	Sound	Defective	1	1	
MH 7-10 MH 7-11	Complete Complete	Sound Sound	Sound Sound	Sound Sound	Sound Sound	Sound Sound	Sound Sound	Sound Sound	0	0	
MH 7-11 MH 7-12	Complete	Sound	Sound	Sound	Sound	Sound	Sound	Sound	1	0	
MH 7-2	Complete	Sound	Sound	Sound	NA - No Cone	Sound	Sound	Sound	0	0	
MH 7-3	Complete	Sound	Sound	Sound	Sound	Sound	Sound	Sound	1	0	
MH 7-4 MH 7-5	Complete Complete	Sound Sound	Sound Sound	Sound Sound	Sound Sound	Sound Sound	Sound Sound	Sound Sound	1 0	0	
MH 7-5 MH 7-6	Complete	Sound	Sound	Sound	Sound	Sound	Sound	NA - No Channel	0	0	
MH 7-7	Complete	Sound	Sound	Sound	Sound	Sound	Sound	Sound	0	0	
MH 7-8	Complete	Sound	Sound	Sound	Sound	Sound	Sound	Sound	0	0	
MH 7-9 MH 8-1	Complete Complete	Sound Sound	Sound	Sound Sound	Sound NA - No Cone	Sound Sound	Sound Sound	Sound	0	0	
MH 8-1 MH 8-2	Complete	Sound	Sound Sound	Sound	NA - No Cone NA - No Cone	Sound	Sound	Sound Sound	1	0	
MH 8-3	Complete	Sound	Sound	Sound	Sound	Sound	Sound	Sound	0	0	
MH 8-4	Complete	Sound	Sound	Sound	Sound	Sound	Sound	Sound	1	0	
MH 9-1-A	Complete	Sound	Sound	Sound	Sound	Sound	NA - No Bench	NA - No Channel	1	0	
MH 9-1-C MH 9-3	Complete Complete	Sound Sound	Sound Sound	Sound Sound	Sound Sound	Sound Sound	Sound Sound	Sound Sound	1	0	
MH-6-10-A	Complete	Sound	Corroded	Sound	Sound	Sound	Sound	Sound	0	1	
MH-6-12-A	Complete	Sound	Sound	Sound	Sound	Sound	Sound	Sound	0	0	
MH 13-1	Incomplete										
MH 13-1-B MH 7-12-A	Incomplete Incomplete - Not Accessible										
MH 7-12-A MH 7-13	Incomplete - Not Accessible										
•											

#### Attachment B. Manhole Database

Facility ID	Inspection Status	Cover Condition	Frame Condition	Chimney Condition	Cone Condition	Wall Condition	Bench Condition	Channel Condition	Count of Infiltration Staining Observations	Count of Defective + Corroded	Replace or Rehabilitation?
MH 7-13-A	Incomplete - Not Accessible										
MH 7-14	Incomplete - Not Accessible										
MH 0-2	Incomplete - Not Found										
MH 1-1	Incomplete - Not Found										
MH 1-2	Incomplete - Not Found										
MH 13-1-B	Incomplete - Not Found										
MH 14-1	Incomplete - Not Found										
MH 15-3	Incomplete - Not Found										
MH 15-5	Incomplete - Not Found										
MH 4-7	Incomplete - Not Found										
MH 4-9	Incomplete - Not Found										
MH 5-11	Incomplete - Not Found										
MH 5-3	Incomplete - Not Found										
MH 6-10	Incomplete - Not Found										
MH 9-4	Incomplete - Not Found										